



DIMENSION SCHEDULE								
PIPE DIA.	A	B	C	D	E	F	G	APPROX. WEIGHT
12"	36"	30"	54"	40"	36"	22"	78"	5445 LBS.
15"	48"	30"	60"	45"	37.5"	22"	92"	6400 LBS.
18"	48"	30"	60"	45"	39"	22"	92"	6400 LBS.
24"	60"	36"	64"	48"	42"	26"	112"	7250 LBS.
30"	72"	36"	72"	54"	45"	26"	124"	9276 LBS.
36"	78"	48"	78"	60"	48"	35"	144"	11623 LBS.
48"	84"	48"	90"	66"	54"	35"	150"	12402 LBS.
SPECIAL SIZES NOT LISTED CAN BE MFG. UPON REQUEST								

NOTES :

- * ALL EXPOSED EDGES TO HAVE 1" BEVELED CORNERS
- * APRON BY CONTRACTOR IN FIELD
- * REINFORCING - NO. 4 BARS AT 12" O.C.E.W.
- * CONCRETE TO TEST 4000 PSI @ 28 DAYS

Precast Manufacturing Co. , LLC
 187 Strykers Road Phillipsburg , N.J. 08865
 Tel. (908) 454-2122 - Fax (908) 454-0512

CONT.		
JOB		
WINGWALL WITH FOOTING		
DATE	DRAWN BY	DRAWING NO.
1 / 17	CLASSIC DESIGN	9-3