

BAR REINFORCEMENT

<u>DEPTH BELOW TOP OF GRADE</u>	<u>HORIZONTAL REINF.</u>	<u>VERTICAL REINF.</u>	<u>WALL THICKNESS</u>
0' TO 10'-0"	#4 @ 10" O.C.	#4 @ 18" O.C.	6"
10'-1" TO 15'-0"	#4 @ 8" O.C.	#4 @ 18" O.C.	6"
15'-1" TO 20'-0"	#4 @ 6" O.C.	#4 @ 18" O.C.	6"

REINFORCING SHOWN FOR PRECAST INLETS IS THE MINIMUM REQUIRED.
ADDITIONAL REINFORCING FOR HANDLING IS THE RESPONSIBILITY OF
THE CONTRACTOR.

WWF REINFORCEMENT

<u>DEPTH BELOW TOP OF GRADE</u>	
0' TO 10'-0"	WWF 3X6 W6 WIRES SPACED AT 3" TO RUN HORIZONTAL IN ALL CASES.
10'-1" TO 15'-0"	WWF 3X6 W6 ADD #3 BAR @ 18" HORIZONTAL.
15'-1" TO 20'-0"	WWF 3X6 W6 ADD #3 BAR @ 9" HORIZONTAL. OR ADD #4 BAR @ 15" HORIZONTAL.

Precast Manufacturing Co. , LLC
187 Strykers Road Phillipsburg , N.J. 08865
Tel. (908) 454-2122 - Fax (908) 454-0512

CONT.

JOB

N.J. CONCRETE INLETS REINF. SCHED.

DATE

DRAWN BY

DRAWING NO.

1 / 17

CLASSIC DESIGN

2-RS