

DWG.NO.	GALLON CAPACITY	A	B	C	D	E	F	WEIGHTS		
								BASE	WALLS	ROOF
4-500	500	3'-0"	6'-0"	4'-6"	3'-11"	3'-9"	4'-2"	2,100 LBS	1,500 LBS/FT	2,814 LBS
4-750	750	4'-0"	6'-6"	5'-0"	4'-2"	4'-0"	4'-5"	2,812 LBS	1,725 LBS/FT	3,769 LBS
4-1000	1000	4'-6"	8'-0"	5'-0"	4'-2"	4'-0"	4'-5"	3,712 LBS	2,025 LBS/FT	4,975 LBS
4-1250	1250	4'-6"	9'-6"	5'-0"	4'-2"	4'-0"	4'-5"	4,331 LBS	2,250 LBS/FT	5,804 LBS
4-1500	1500	5'-0"	10'-0"	5'-0"	4'-3"	4'-0"	4'-6"	4,950 LBS	2,400 LBS/FT	6,633 LBS
4-2000	2000	5'-0"	10'-0"	6'-6"	5'-9"	5'-6"	6'-0"	4,950 LBS	2,400 LBS/FT	6,633 LBS
4-2500	2500	6'-0"	12'-0"	5'-9"	5'-0"	4'-9"	5'-3"	6,825 LBS	2,850 LBS/FT	9,145 LBS
4-3000	3000	6'-0"	12'-0"	6'-9"	6'-0"	5'-9"	6'-3"	6,825 LBS	2,850 LBS/FT	9,145 LBS

4-3500	3500	7'-0"	16'-0"	5'-6"	4'-5"	4'-2"	4'-8"
4-4000	4000	7'-0"	16'-0"	6'-0"	5'-1"	4'-10"	5'-4"
4-4500	4500	7'-0"	16'-0"	6'-6"	5'-8"	5'-5"	5'-11"
4-5000	5000	7'-0"	16'-0"	7'-0"	6'-3"	6'-0"	6'-6"
4-5500	5500	7'-0"	16'-0"	7'-8"	6'-10"	6'-7"	7'-1"
4-6000	6000	7'-0"	16'-0"	8'-6"	7'-8"	7'-5"	7'-11"
4-6500	6500	7'-0"	16'-0"	9'-0"	8'-0"	7'-9"	8'-3"
4-7000	7000	7'-0"	16'-0"	9'-6"	8'-7"	8'-4"	8'-10"
4-7500	7500	7'-0"	16'-0"	10'-0"	9'-2"	8'-11"	9'-5"
4-8000	8000	7'-0"	16'-0"	10'-6"	9'-9"	9'-6"	10'-0"

10,200 LBS 3,600 LBS/FT 13,668 LBS

Precast Manufacturing Co. , LLC
 187 Strykers Road Phillipsburg , N.J. 08865
 Tel. (908) 454-2122 - Fax (908) 454-0512

CONT.

JOB

GREASE TRAP SCHEDULE

DATE

DRAWN BY

DRAWING NO.

1 / 17

CLASSIC DESIGN

4 A
SCHEDULE