



## NOTES :

- \* CONCRETE TO TEST 4000 PSI @ 28 DAYS
- \* REBARS ASTM A-615-40
- \* SIZE AND SHAPE OF OPENING TO SUIT
- \* APPROX. WEIGHT = 7,500 LBS.
- \* LOAD RATING HS20

| Precast Manufacturing Co. , LLC   |  |                |  |         |     |
|---|--|----------------|--|---------|-----|
| 187 Strykers Road Phillipsburg , N.J. 08865<br>Tel. (908) 454—2122 — Fax (908) 454—0512 |  |                |  |         |     |
| Tel. (908) 454-2122 - Fax (908) 454-0512  |  |                |  |         |     |
| CONT.   |  |                |  |         |     |
| JOB   |  |                |  |         |     |
| 10'-0" DIA. TOP SLAB  |  |                |  |         |     |
| DATE  |  | DRAWN BY       |  | DRAWING | NO. |
| 1 / 17  |  | CLASSIC DESIGN |  | 710-T   |     |