



DIMENSION SCHEDULE

- A = 12" THRU 48"
- B = LENGTH AS REQUIRED
4'-0" MINIMUM
- C = DEPTH AS REQUIRED
- D = 6" OR 8"*

* = OTHER SIZES AVAILABLE AS REQUIRED

NOTE :

- * GALVANIZED STEEL GRATING ALSO AVAILABLE
- * CONCRETE TO TEST 4000 PSI @ 28 DAYS
- * REINFORCEMENT :

Precast Manufacturing Co. , LLC
 187 Strykers Road Phillipsburg , N.J. 08865
 Tel. (908) 454-2122 - Fax (908) 454-0512

CONT.		
JOB		
<i>TRENCH DRAIN</i>		
DATE	DRAWN BY	DRAWING NO.
1 / 17	CLASSIC DESIGN	140